



Express Rail Link (XRL) - Seamless Integration with Mainland's High Speed Rail Network

Leung Chi Lap
General Manager – XRL E&M
MTR Corporation
23 October 2017

Agenda

- 1. Key Project Information**
- 2. Interface with Mainland**
- 3. High Speed Train**
- 4. Railway Systems**
- 5. Present Challenges**




1. Key Project Information

Mainland High Speed Network Plan in 2016 (八縱八橫)



Total network:
20,000km (2017)
30,000km (2020)
38,000km (2025)

Guangzhou - Shenzhen - Hong Kong Express Rail Link



XRL Alignment

Tunnel Alignment & Facilities

- Vent Building (VB)
- ▲ Emergency Access Point (EAP)



Shek Kong Stabling Sidings & Emergency Rescue Station



West Kowloon Terminus






2. Interfaces with the Mainland

Mainland E&M Interface Designs

- Mainland Interface Design by 4th Design Institute (鐵四院) and approved by China Railway Corporation
- Hong Kong / Mainland communication links approved by Ministry of Industry and Information Technology
- Follow MTR design management practice : Interface Requirement Specification, Detailed Interface Specification, Detailed Interface Test Plan, etc

Train Traffic Control Boundary for HK Section

- Adopted Regional Control (屬地管理) for XRL in 2012



Centralized Control in HK OCC


- Line overview for traffic monitoring from WKT to Guangzhou South



Centralized Control in HK OCC

- Traffic Control, Traction Power, Tunnel ECS
- Communications – CCTV, FAS(COM), O&M radio, GSM-R, video conferencing and Emergency Communication System
- Fallback control at WKT SCR in case of HK OCC failure


Shek Kong Operations Control Room




West Kowloon Station Control Room



Fall Back




Cross-boundary Tunnels



Evacuation Walkway in Tunnel

- Cross passage at 250m interval, and doors 4 hours fire-rated
- Cross passage doors normally locked with remote controlled from OCC
- HK section adopts high level evacuation walkway while Mainland section adopts low level evacuation walkway





3. High Speed Train

XRL Train Design from Hong Kong

- Nine 8-car trains procured from Qingdao Sifang 青島四方
- Follow design baseline of CRH380A type developed by Sifang (CRH ~ China Railway High Speed 和諧號)
- New aesthetic interior and exterior outlook
- Type Testing at Hangzhou-Changsha section (杭州~長沙段)
- Technical enhancements on top of the proven CRH380A design following specific MTR requirements
 - Number of passengers: 579 seats + 2 wheel chair space
 - Design speed : 350km/h
 - Operating speed (mainland section): 300km/h
 - Operating speed (HK section): 200km/h



3rd party trains from Mainland

- Mainland train type certification to operate in HK
 - Over 10 train types, i.e. CRH380A/AL, CRH 380B/BL, CRH 1A/1B/1E, CRH1A-A, CRH2A/2B/2E, CRH3C, CR400AF, CR400BF
- Kinematic Envelope endorsed by Expert Review Panel (專家評審) to accommodate evacuation walkway and other specific areas,



3rd party trains certification framework

- Kinematic Envelope endorsed by Expert Review Panel (專家評審) to accommodate evacuation walkway and other specific areas
- Certification process :-
 - Preparation Stage to identify the verification items, review technical documentation, prepare test procedure
 - Verification Stage to perform inspection and testing in the Mainland and Hong Kong
 - Approval Stage to compile technical assessment report and obtain approval from the regulatory authority




4. Railway Systems

Signalling System

- **Chinese Train Control System (CTCS) to ensure interoperability with Mainland infrastructure and trains**
- **CTCS-2 based on ETCS Level 1**
 - Train-track communications via track circuit and balise
- **CTCS-3 based on ETCS Level 2**
 - GSM-R radio for train-track communications for 350km/h design speed
- **CTCS-3 train using CTCS-2 as back up in case of failure**


Signalling System for CTCS-3

- Radio block centre (RBC) issues movement authority to train based real time information – position, speed, alignment, route, temporary speed restriction
- On-board computer provides target speed for driver




Backbone Transmission Network

- Dedicated fibre optic cables via cross-boundary tunnel
- Transmission of voice and data with cable route diversity
- Dark fibre cables provided for Signalling, MCS, Ticketing



Backbone Transmission Network




Radio Communications Systems : GSM-R

- System function
 - 2-way data transmission channel for signaling CTCS-3 train control at high speed based on GSM technology
 - Seamless wireless voice and data communication for train crew and OCC
- Same frequency band as the Mainland :
 - 885-889MHz Up-link, 930-934MHz Down-link
- Base station subsystem in HK to connect with Mainland GSM-R core network via optical fibre
- Coordination with HK Mobile Network Operator to ensure no interference



GSM-R radio system overview



Main Control System

- **Hong Kong Main Control System interfaces with 3 subsystems of Mainland :**
 - **Fire Alarm System (FAS) for Futian Station and trackside services**
 - **PSCADA for 25kV Traction Power and Overhead Line equipment**
 - **Monitor 25kV traction equipment without control**
 - **Building Automation System (BAS) for tunnel lighting, exit signs, cross passage door, sump pumps and tunnel ventilation fans**
 - **Tunnel Ventilation Fan coordinated control mode via MCS/BAS interface**




5. Key Challenges

Key Challenges

- **Numerous stakeholders :**
 - **China Railway Corporation, Guangzhou Rail Corporation, Mainland Guang-Shen-Gang project company, 4th Design and Survey Institute, China Academy of Railway Sciences (CARS), Government of Hong Kong SAR**
 - **3-tier hierarchy of coordination committees, subcommittees and working groups**
 - **Dedicated T&C Command Centre**

Mainland Liaison – Committee, Subcommittees and Working Groups



Progress of Cross Boundary Dynamic T&C

- Guangzhou OCC and HK OCC connected
- Cross boundary dynamic T&C commenced in July 2017
- Speed Verification tests at 220km/h for infrastructure using the Comprehensive Inspection Train successfully completed
- Signaling dynamic tests by 841A and CARS 鐵科院 in progress
- Type testing on Hong Kong Train completed
- Dynamic T&C to be completed by end 2017
- XRL opening expected Q3/2018



Q & A